

Kerala Transport Development Finance Corporation Limited
6th Floor, Trans Towers, Vazhuthacaud, Thiruvananthapuram 695 014

Quotation Notice

Quotation No.01 /BOTP/KTDFC/KKD/2019

Name of work	Period of Completion	EMD	Estimated PAC
Providing G.I Sheet fencing in the damaged portion of compound wall at KSRTC Bus Terminal Complex. Kozhikode.	1 month	Rs. 1650/-	Rs.65,000

Sealed competitive quotations are invited for the work of " Providing G.I Sheet fencing in the damaged portion of compound wall at KSRTC Bus Terminal Complex. Kozhikode". Quotation forms will be available at the KTDFC website www.ktdfc.com from **28.01.2019** Last date of receipt of quotation will be **07.02.2019 at 11 A.M.** Quotation will be opened on **07.02.2019 at 3.00 PM** . For more details please visit www.ktdfc.com. For any further details, please contact KTDFC (Ph.0471 2327881)

Date: 22.01.2019


Principal Project Consultant

Name of Work : Providing G.I Sheet fencing in the damaged portion of compound wall at KSRTC Bus Terminal Complex. Kozhikode.

Quotation schedule

Sl No	Description of work	Quantity	Unit	Rate	Amount
1	Steel work in built up tubular (Round, square or rectangular hollow tubes etc) sections etc, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	142	kg	Rs./ kg	
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work including all coat and conveyance of all materials and labour charges.	10	m2	Rs..... /m2	
3	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge)0.50mm (+0.05%) , total coated thickness with zinc coating of 120grams per sqm as per IS.277, in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge . The sheet shall be fixed using self drilling/self tapping screws of size (5.5 x 55mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	28	m2	Rs..... /m2	
4	Providing and fixing PVC pipes including fixing the pipe with clamps/ clips at 1.00m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer -in- Charge using departmental pipes 75mm and 50mm dia .	300	m	Rs..... /m	
	Total				

bf