

KERALA TRANSPORT DEVELOPMENT FINANCE CORPORATION LIMITED

KSRTC Bus Terminal Complex, Thampanoor, Thiruvananthapuram – Construction of Compound
wall along the Western Boundary Adjacent to the Canal

TENDER No. 35/BOTP/KTDFC/TPNR/2015

PART – II

PRICE BID

**KTDFC
Trans Towers
Thiruvananthapuram-14**

Principal Project Consultant

Part IV						
Tender Schedule						
KSRTC Bus Terminal Complex, Thampanoor, Thiruvananthapuram – Construction of Compound wall along the Western Boundary Adjacent to the Canal						
Sl No.	Description of work	Qty	Unit	Rate (figures)	Rate (words)	Amount
1	Earth work in excavation in all kinds of soil by mechanical means(Hydraulic excavation) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10sqm on plan) including disposal of excavated earth lead upto 50m and lift upto 1.5m, disposal earth to be levelled and neatly dressed.	37.00	m ³			
2	Cement concrete 1:4:8 using 40mm normal size including watering, curing etc complete.	9.00	m ³			
3	Random rubble masonry in CM 1:6 with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement:6 course sand: 12 graded stone aggregate 20mm nominal size)upto plinth level.	37.00	m ³			
4	Cement Solid block masonry in CM 1:6 using 40x20x15cm solid block including cost and conveyance of all materials.	39.00	m ³			
5	Plastering with cement mortar 1:5, 12mm thick one coat floated hard and trowelled smooth for both sides including cost, conveyance and labour etc.	534.00	m ²			
6	White cement washing two coats including cost and conveyance of all materials, labour charges etc complete.	534.00	m ²			
Grand Total						